

Sewer Rehabilitation - Infiltration/Inflow Repairs

LaDEQ CWSRF CS221741-01

City of Hammond

11-Oct-2013

Bid Item	Description	Contract Quantity	Insituform Technologies	
			UNIT PRICE	EXTENSION
1.	Mobilization	1 EA	\$ 22,000.00	\$ 22,000.00
2.	8" Cured-in-Place Pipe (CIPP) lining	53,000 LF	22.00	1,166,000.00
3.	10" CIPP Lining	450 LF	26.00	11,700.00
4.	12" CIPP Lining	3,700 LF	31.00	114,700.00
5.	15" CIPP Lining	6,400 LF	38.00	243,200.00
6.	18" CIPP Lining	1,450 LF	55.00	79,750.00
7.	Restore Remote Service	1,000 EA	1.00	1,000.00
8.	Trim Protuding Service	200 EA	75.00	15,000.00
9.	8" Point Repair (all depths)	150 EA	1,400.00	210,000.00
10.	Extend 8" Point Repair	800 LF	5.00	4,000.00
11.	10" Point Repair (all depths)	2 EA	2,150.00	4,300.00
12.	Extend 10" Point Repair	20 LF	90.00	1,800.00
13.	12" Point Repair (all depths)	8 EA	2,300.00	18,400.00
14.	Extend 12" Point Repair	50 LF	75.00	3,750.00
15.	15" Point Repair (all depths)	3 EA	2,430.00	7,290.00
16.	Extend 15" Point Repair	30 LF	70.00	2,100.00
17.	18" Point Repair (all depths)	4 EA	4,650.00	18,600.00
18.	Extend 18" Point Repair	40 LF	100.00	4,000.00
19.	Install Service Line Point Repair(4"/6")	360 EA	500.00	180,000.00
20.	Extend Service Line Point Repair (4"/6")	8,000 LF	13.00	104,000.00
21.	Install 4"(6") SS Cleanout over exist. svc.	400 EA	675.00	270,000.00
22.	Service lateral (4"/6") CCTV & Cleaning	900 EA	100.00	90,000.00
23.	Install Slab Sod + Root Zone	2,000 SY	14.50	29,000.00
24.	Svc. Lateral (4"/6") transition at SS Main	50 EA	1.00	50.00
25.	Svc. Lateral (4"/6") CIPP; ≤ 5'	50 EA	2,100.00	105,000.00
26.	Abandon Point Repair (all depths)	5 EA	700.00	3,500.00
27.	Patch, Seal, & Polymeric Line SSMH	300.0 VF	180.00	54,000.00
28.	Patch, Seal, & Cementitious Line SSMH	1,100.0 VF	97.00	106,700.00
29.	Re-build SSMH Invert	30 EA	250.00	7,500.00
30.	Re-set and Seal SSMH Cover	24 EA	260.00	6,240.00
31.	Replace SSMH Frame & Cover	60 EA	690.00	41,400.00
32.	Install new SS Manhole, complete	150.0 VF	300.00	45,000.00
33.	Remove/replace Pavement (6" th.-reinf.)	1,600.0 SY	82.00	131,200.00
34.	Remove/replace Pavement (8" th.-unreinf.)	2,000.0 SY	130.00	260,000.00
35.	Haul-in/compact select BACKFILL	1,000 CY	16.50	16,500.00
36.	Haul-in/grade LIMESTONE	1,200 TN	48.50	58,200.00
37.	Clean & CCTV SS lines (6" - 12")	1,000 LF	3.50	3,500.00
38.	Clean & CCTV SS lines (15" - 18")	500 LF	3.50	1,750.00
39.	Smoke Test SS lines (all sizes)	2,500 LF	0.65	1,625.00
40.	Extend CIPP Service Lateral (4"/6"); >5'	1,500 LF	1.00	1,500.00
41.	Miscellaneous Sitework/Aerial-DI crossing	1 EA	42,000.00	42,000.00
BASE BID (items "1." - "41.):			\$	3,486,255.00
<i>Additive Alternate No. One (1):</i>				
24A.	Svc. Lateral (4"/6") transition at SS Main	150 EA	\$ 1.00	\$ 150.00
25A.	Svc. Lateral (4"/6") CIPP; ≤ 5'	150 EA	2,375.00	356,250.00
40A.	Extend CIPP Service Lateral (4"/6"); >5'	4,500 LF	1.00	4,500.00
ADDITIVE ALTERNATE No. 1 BID (items "24A.", "25A.", & "40A.):			\$	360,900.00
ORIGINAL CONTRACT AMOUNT:			\$	3,847,155.00
Construction Contingencies		19.05%	\$ 3,847,155	732,845.00
"Sewer Rehabilitation - I/I Repairs" Construction Budget			\$	4,580,000.00