


## BID SUMMARY

<b>DRAINAGE IMPROVEMENT [FY2014] FOR THE CITY OF HAMMOND</b>			
<u>Bid Opening:</u> Friday, March 14, 2014, 10:00 a.m.			
<b>BIDDER</b>	Louisiana Contractor License Number	BASE BID Items "1-25"	Bid Rank
<b>1. Command Construction, LLC</b> 3206 Turnbull Drive, Metairie, LA 70002	<b>40038</b>	<b>NO BID</b>	
<b>2. Dieudonne Enterprises, Inc.</b> P. O. Box 23686, New Orleans, LA 70002	<b>45794</b>	<b>NO BID</b>	
<b>3. Hard Rock Construction, LLC</b> 2305 L & A Road, Metairie, LA 70001	<b>24901</b>	<b>NO BID</b>	
<b>4. HCI Construction Group, Inc.</b> 10484 Mammoth Avenue, Baton Rouge, LA 70814	<b>50512</b>	<b>NON-RESPONSIVE</b>	
<b>5. L. King Company, LLC</b> 2450 Florida Avenue SW, Suite B, Denham Springs, LA 70726	<b>42360</b>	\$ <b>463,667.00</b>	<b>6</b>
<b>6. Kort's Construction Services, Inc.</b> 2182 Manton Drive, Covington, LA 70433	<b>49356</b>	\$ <b>426,789.75</b>	<b>5</b>
<b>7. Lawson-Bonet Construction, Inc.</b> P. O. Box 1313, Hammond, LA 70404	<b>39990</b>	\$ <b>299,577.45</b>	<b>1</b>
<b>8. Stranco, LLC</b> 70459 Highway 59, Abita Springs, LA 70420	<b>16724</b>	\$ <b>363,361.25</b>	<b>3</b>
<b>9. Byron E. Talbot Contractor, Inc.</b> 24288 Highway 190, Robert, LA 70455	<b>12198</b>	\$ <b>333,264.75</b>	<b>2</b>
<b>10. Willis Construction Company, LLC</b> P. O. Box 938, Sun, LA 70463	<b>37657</b>	\$ <b>388,624.90</b>	<b>4</b>

NOTES TO BID OPENING:

- (1) HCI Construction Group, Inc. did not acknowledge Addendum No. One (1). Bid considered Non-responsive.

Certified Correct: \_\_\_\_\_

  
Kiley F. Bates, P. E.

**BID TABULATION**

**DRAINAGE IMPROVEMENTS [FY 2014] FOR THE CITY OF HAMMOND**

Bid Opening: Friday, March 14, 2014, 10:00 a.m.

Bid Item	Description	Bid Quantity	Engineer's Estimate		L. King Company, LLC		Kort's Construction Services, Inc		
			Unit Price	Extension	Unit Price	Extension	Unit Price	Extension	
1.	Mobilization	1	EA \$15,000.00	\$15,000.00	\$33,640.00	\$33,640.00	\$30,000.00	\$30,000.00	
2.	Haul-in/compact earthen backfill [vehicular measure]	660	CY	9,240.00	24.90	16,434.00	16.50	10,890.00	
3.	Pipe cleaning (12" - 18" diameter storm drain pipes)	175	LF	8.00	1,400.00	13.20	2,310.00	350.00	
4.	Pipe cleaning (24" - 36" diameter storm drain pipes)	1,100	LF	10.00	11,000.00	7.60	8,360.00	3,300.00	
5.	Clean and access existing catch basin	14	EA	300.00	4,200.00	520.00	7,280.00	1,750.00	
6.	Video storm drain pipes	1,275	LF	3.00	3,825.00	2.60	3,315.00	1.75	2,231.25
7.	Miscellaneous clearing and sitework	1	EA	7,500.00	7,500.00	31,719.00	31,719.00	10,000.00	
8.	Install/open cut 8" PVC	175	LF	15.00	2,625.00	25.60	4,480.00	12.50	2,187.50
9.	Install/open cut 12" PVC	8	LF	20.00	160.00	235.00	1,880.00	32.00	256.00
10.	Install/open cut 15" ACCMP (A)	1,120	LF	45.00	50,400.00	46.50	52,080.00	38.50	43,120.00
11.	Install/open 18" ACCMP (A)	1,750	LF	55.00	96,250.00	53.20	93,100.00	45.00	78,750.00
12.	Install/open 24" ACCMP (A)	850	LF	60.00	51,000.00	61.10	51,935.00	50.00	42,500.00
13.	Install concrete collar	2	EA	300.00	600.00	1,155.00	2,310.00	800.00	1,600.00
14.	Install Type VI catch basin	32	EA	2,000.00	64,000.00	1,670.00	53,440.00	2,750.00	88,000.00
15.	Install Type VIII catch basin	15	EA	1,500.00	22,500.00	2,037.00	30,555.00	2,750.00	41,250.00
16.	Install Type IX catch basin	4	EA	1,000.00	4,000.00	1,568.00	6,272.00	2,750.00	11,000.00
17.	Sawcut pavements (all types)	420	LF	9.00	3,780.00	12.15	5,103.00	6.00	2,520.00
18.	Remove/replace 8" th. street (to include 6" thick unreinforced PCC+2.0" hot AC surfacing)	205	SY	90.00	18,450.00	92.00	18,860.00	115.00	23,575.00
19.	Tie-in new/existing storm drain(s) to new/existing catch basin	3	EA	750.00	2,250.00	1,393.00	4,179.00	850.00	2,550.00
20.	Install slab sodding	400	SY	10.00	4,000.00	12.10	4,840.00	5.00	2,000.00
21.	Haul-in/mix root zone material [pre-sod]	1,900	CF	8.00	15,200.00	1.40	2,660.00	1.00	1,900.00
22.	Haul-in/grade limestone [Type 610 - vehicular measure]	125	TN	50.00	6,250.00	64.00	8,000.00	55.00	6,875.00
23.	Adjust existing valve box/manhole/catch basin	3	EA	700.00	2,100.00	434.00	1,302.00	650.00	1,950.00
24.	Excavate Type I ditch [1.0'W bottom; 2H:1V sideslopes]	150	LF	10.00	1,500.00	11.00	1,650.00	3.50	525.00
25.	Remove/replace 6" th. driveway/sidewalk [6" thick PCC reinforced w/6x6-10/10 WWF]	253	SY	60.00	15,180.00	71.00	17,963.00	70.00	17,710.00
				<b>BASE BID [Item "1.-25."]:</b>		<b>\$412,410.00</b>		<b>\$426,789.75</b>	
				<b>\$463,667.00</b>					

**BID TABULATION**

**DRAINAGE IMPROVEMENTS [FY 2014] FOR THE CITY OF HAMMOND**

Bid Opening: Friday, March 14, 2014, 10:00 a.m.

Engineer: Spangler Engineering, LLC, Consulting Civil Engineers

Bid Item	Description	Lawson-Bonet Construction, Inc.		Stranco, LLC		Byron E. Talbot Contractor, Inc.		Willis Construction Company, LLC	
		Unit Price	Extension	Unit Price	Extension	Unit Price	Extension	Unit Price	Extension
1.	Mobilization	\$10,000.00	\$10,000.00	\$16,000.00	\$16,000.00	\$28,000.00	\$28,000.00	\$44,370.00	\$44,370.00
2.	Haul-in/compact earthen backfill [vehicular measure]	13.30	8,778.00	10.00	6,600.00	15.00	9,900.00	15.00	9,900.00
3.	Pipe cleaning (12" - 18" diameter storm drain pipes)	2.50	437.50	2.25	393.75	2.20	385.00	2.50	437.50
4.	Pipe cleaning (24" - 36" diameter storm drain pipes)	3.75	4,125.00	3.30	3,630.00	3.30	3,630.00	3.50	3,850.00
5.	Clean and access existing catch basin	168.00	2,352.00	137.50	1,925.00	138.00	1,932.00	145.00	2,030.00
6.	Video storm drain pipes	2.30	2,932.50	1.90	2,422.50	1.95	2,486.25	2.00	2,550.00
7.	Miscellaneous clearing and sitework	33,695.00	33,695.00	12,500.00	12,500.00	31,500.00	31,500.00	3,000.00	3,000.00
8.	Install/open cut 8" PVC	9.50	1,662.50	32.00	5,600.00	16.00	2,800.00	9.80	1,715.00
9.	Install/open cut 12" PVC	24.00	192.00	40.00	320.00	40.00	320.00	82.50	660.00
10.	Install/open cut 15" ACCMP (A)	21.30	23,856.00	37.00	41,440.00	26.00	29,120.00	22.50	25,200.00
11.	Install/open 18" ACCMP (A)	25.20	44,100.00	44.00	77,000.00	33.00	57,750.00	30.70	53,725.00
12.	Install/open 24" ACCMP (A)	36.80	31,280.00	54.00	45,900.00	37.00	31,450.00	40.50	34,425.00
13.	Install concrete collar	399.00	798.00	600.00	1,200.00	400.00	800.00	2,000.00	4,000.00
14.	Install Type VI catch basin	1,512.40	48,396.80	2,050.00	65,600.00	1,400.00	44,800.00	3,275.00	104,800.00
15.	Install Type VIII catch basin	1,643.25	24,648.75	1,450.00	21,750.00	1,550.00	23,250.00	2,635.00	39,525.00
16.	Install Type IX catch basin	1,218.85	4,875.40	1,450.00	5,800.00	1,200.00	4,800.00	2,805.00	11,220.00
17.	Sawcut pavements (all types)	6.45	2,709.00	10.00	4,200.00	7.50	3,150.00	6.00	2,520.00
18.	Remove/replace 8" th. street (to include 6" thick unreinforced PCC+2.0" hot AC surfacing)	69.00	14,145.00	100.00	20,500.00	75.00	15,375.00	80.00	16,400.00
19.	Tie-in new/existing storm drain(s) to new/existing catch basin	1,275.00	3,825.00	600.00	1,800.00	1,000.00	3,000.00	2,000.00	6,000.00
20.	Install slab sodding	8.90	3,560.00	6.00	2,400.00	4.40	1,760.00	4.00	1,600.00
21.	Haul-in/mix root zone material [pre-sod]	4.20	7,980.00	1.00	1,900.00	3.25	6,175.00	0.65	1,235.00
22.	Haul-in/grade limestone [Type 610 - vehicular measure]	60.00	7,500.00	48.00	6,000.00	50.00	6,250.00	45.00	5,625.00
23.	Adjust existing valve box/manhole/catch basin	258.00	774.00	600.00	1,800.00	600.00	1,800.00	500.00	1,500.00
24.	Excavate Type I ditch [1.0'W bottom; 2H:1V sideslopes]	3.40	510.00	10.00	1,500.00	8.00	1,200.00	5.00	750.00
25.	Remove/replace 6" th. driveway/sidewalk [6" thick PCC reinforced w/6x6-10/10 WWF]	65.00	16,445.00	60.00	15,180.00	85.50	21,631.50	45.80	11,587.40
<b>BASE BID [Item "1.-25."]:</b>			<b>\$299,577.45</b>		<b>\$363,361.25</b>		<b>\$333,264.75</b>		<b>\$388,624.90</b>

Notes to Bid Opening:

(1) HCI Construction Group, Inc. did not acknowledge Addendum No. One (1). Bid considered Non-responsive.

Certified Correct: Kiley F. Bates  
 Kiley F. Bates, P. E.

14-Mar-14  
 Date