

## BID SUMMARY

<b>Pine Hill Forest Sewer Extension</b> for the City of Hammond			
<u>Bid Opening:</u> Friday, October 16, 2015, 10 a.m.		<u>Engineer:</u> Spangler Engineering, LLC	
<b>BIDDER</b>	La. Contr. License No.	BASE BID [items "1." - "19."]	Bid Rank
1. <b>Byron E. Talbot Contractor, Inc.</b> 24288 Hwy. 190; Robert, LA 70455	<b>12198</b>	NO BID	
2. <b>Global Industrial Contractors, LLC</b> P. O. Box 706; Port Allen, LA 70767	<b>50096</b>	\$ 395,225.50	[ 3 ]
3. <b>Greenbriar Digging Service</b> 1941 Hwy. 550 NW; Brookhaven, MS 39601	<b>30270</b>	\$ 374,352.00	[ 2 ]
4. <b>Hawkmoon Construction Service, LLC</b> 68361-5 Commercial Way S; Mandeville 70471	<b>58082</b>	NO BID	
5. <b>Lawson-Bonet Construction, Inc.</b> P. O. Box 1313; Hammond, LA 70404	<b>39990</b>	\$ 442,621.00	[ 6 ]
6. <b>Magnolia Construction Co., LLC</b> P. O. Box 66096; Baton Rouge, LA 70896	<b>38553</b>	\$ 505,933.00	[ 7 ]
7. <b>Mitchell Contracting, Inc. (a)</b> 545 Southdown Loop; Covington, LA 70433	<b>58085</b>	\$ 366,588.00	[ 1 ]
8. <b>NCMC</b> P. O. Box 83760; Baton Rouge, LA 70884	<b>8999</b>	\$ 414,033.00	[ 4 ]
9. <b>Robert Foster Construction, LLC</b> 22240 Savannah Lane; Covington, LA 70435	<b>53791</b>	NO BID	
10. <b>Subterranean Construction, LLC</b> P. O. Box 588; Mandeville, LA 70470	<b>34191</b>	\$ 428,458.00	[ 5 ]
11. <b>Wallace C. Drennan, Inc.</b> 1500 Nine Mile Point; Westwego, LA 70094	<b>1033</b>	NO BID	
12.			

**NOTES TO BID OPENING:**

(a) Error in bid total: "\$364,088.00" written vs. **\$366,588.00 actual**

(b) \_\_\_\_\_

Certified Correct: \_\_\_\_\_

  
T. C. Spangler, Jr., P.E.

Date: 16-Oct-2015

# Bid Tabulation


## Pine Hill Forest Sewer Rehabilitation for the City of Hammond

Bid Opening: Friday, October 16, 2015, 10:00 a.m.

Engineer: Spangler Engineering, LLC

Bid Item	Description	Bid Quantity	Engineer's Estimate			Mitchell Contracting (a)			Greenbriar Digging Svc.		
			Unit Price	Extension	Unit Price	Extension	Unit Price	Extension	Unit Price	Extension	
1.	Mobilization	1 EA	\$ 5,000.00	\$ 5,000.00	\$ 2,500.00	\$ 2,500.00	\$ 23,000.00	\$ 23,000.00			
2.	Install/Open Cut 8" SS Main - 0' - 6' deep	4,020 LF	28.00	112,560.00	24.00	96,480.00	25.00	100,500.00			
3.	Install/Open Cut 8" SS Main - 6' - 10' deep	540 LF	32.00	17,280.00	26.00	14,040.00	30.00	16,200.00			
4.	Install new SSMH complete	17 EA	2,500.00	42,500.00	2,000.00	34,000.00	2,800.00	47,600.00			
5.	Install 8x4 SS Wyes	80 EA	100.00	8,000.00	90.00	7,200.00	150.00	12,000.00			
6.	Install/open cut 4" PVC SS Service Lateral	1,150 LF	8.00	9,200.00	10.00	11,500.00	12.00	13,800.00			
7.	Jack & bore 4" PVC SS service lateral	1,000 LF	15.00	15,000.00	20.00	20,000.00	20.00	20,000.00			
8.	Install/open cut 6" PVC SS Service Lateral	40 LF	14.00	560.00	12.00	480.00	15.00	600.00			
9.	Jack & bore 6" PVC SS service lateral	20 LF	25.00	500.00	24.00	480.00	25.00	500.00			
10.	Tie-in exist. Svc. to new 4"/6" svc. [incl. cleanout]	70 EA	250.00	17,500.00	550.00	38,500.00	250.00	17,500.00			
11.	Install Cleanout on new 4"/6" SS Svc. Lateral	70 EA	200.00	14,000.00	150.00	10,500.00	170.00	11,900.00			
12.	Miscellaneous Clearing & Sitework	1 EA	5,000.00	5,000.00	4,500.00	4,500.00	5,000.00	5,000.00			
13.	Remove/replace Pavement (6" th.) - 30 driveways	686.0 SY	65.00	44,590.00	78.00	53,508.00	42.00	28,812.00			
14.	Remove/replace Pavement (8" th.) - 5 street xings	260.0 SY	85.00	22,100.00	80.00	20,800.00	60.00	15,600.00			
15.	Haul-in/compact BACKFILL (truck measure)	60 CY	15.00	900.00	10.00	600.00	11.00	660.00			
16.	Haul-in/grade LIMESTONE (truck measure)	260.0 TN	50.00	13,000.00	60.00	15,600.00	46.00	11,960.00			
17.	Sawcut pavements (4" - 8" thick)	1,600 LF	7.00	11,200.00	4.00	6,400.00	6.00	9,600.00			
18.	Haul-in/fine grade ROOT ZONE matl. (1.0" thick)	3,850 CF	1.00	3,850.00	1.00	3,850.00	1.50	5,775.00			
19.	Install Slab SOD	5,130 SY	6.00	30,780.00	5.00	25,650.00	6.50	33,345.00			
<b>Total BASE BID [items "1." through "19."]:</b>			<b>\$</b>	<b>373,520.00</b>	<b>\$</b>	<b>366,588.00</b>	<b>\$</b>	<b>374,352.00</b>			

Notes to Bid Opening: (a) Error in bid total: "\$364,088.00" written vs. \$366,588.00 actual

  
 Certified Correct: \_\_\_\_\_ Date: 16-Oct-2015  
 T. C. Spangler, Jr., P.E.

# Bid Tabulation

## Pine Hill Forest Sewer Rehabilitation

for the City of Hammond

Bid Opening: Friday, October 16, 2015, 10:00 a.m.

Engineer: Spangler Engineering, LLC

Bid Item	Description	Bid Quantity	Global Industrial		NCMC, LLC		Subterranean Constr.	
			Unit Price	Extension	Unit Price	Extension	Unit Price	Extension
1.	Mobilization	1 EA	\$ 16,120.00	\$ 16,120.00	\$ 40,329.00	\$ 40,329.00	\$ 22,000.00	\$ 22,000.00
2.	Install/Open Cut 8" SS Main - 0' - 6' deep	4,020 LF	22.25	89,445.00	19.20	77,184.00	37.00	148,740.00
3.	Install/Open Cut 8" SS Main - 6' - 10' deep	540 LF	34.10	18,414.00	20.30	10,962.00	52.00	28,080.00
4.	Install new SSMH complete	17 EA	2,256.00	38,352.00	2,243.00	38,131.00	2,500.00	42,500.00
5.	Install 8x4 SS Wyes	80 EA	37.00	2,960.00	35.50	2,840.00	42.00	3,360.00
6.	Install/open cut 4" PVC SS Service Lateral	1,150 LF	24.40	28,060.00	19.60	22,540.00	10.00	11,500.00
7.	Jack & bore 4" PVC SS service lateral	1,000 LF	18.80	18,800.00	18.53	18,530.00	20.00	20,000.00
8.	Install/open cut 6" PVC SS Service Lateral	40 LF	28.00	1,120.00	20.30	812.00	12.00	480.00
9.	Jack & bore 6" PVC SS service lateral	20 LF	19.00	380.00	23.40	468.00	32.00	640.00
10.	Tie-in exist. Svc. to new 4"/6" svc.[incl. cleanout]	70 EA	299.00	20,930.00	296.00	20,720.00	360.00	25,200.00
11.	Install Cleanout on new 4"/6" SS Svc. Lateral	70 EA	353.00	24,710.00	224.00	15,680.00	200.00	14,000.00
12.	Miscellaneous Clearing & Sitework	1 EA	3,900.00	3,900.00	21,650.00	21,650.00	6,000.00	6,000.00
13.	Remove/replace Pavement (6" th.) - 30 driveways	686.0 SY	67.00	45,962.00	78.00	53,508.00	58.00	39,788.00
14.	Remove/replace Pavement (8" th.) - 5 street xings	260.0 SY	100.00	26,000.00	97.00	25,220.00	80.00	20,800.00
15.	Haul-in/compact BACKFILL (truck measure)	60 CY	22.75	1,365.00	30.30	1,818.00	30.00	1,800.00
16.	Haul-in/grade LIMESTONE (truck measure)	260.0 TN	61.50	15,990.00	62.40	16,224.00	48.00	12,480.00
17.	Sawcut pavements (4" - 8" thick)	1,600 LF	8.70	13,920.00	6.50	10,400.00	4.20	6,720.00
18.	Haul-in/fine grade ROOT ZONE matl. (1.0" thick)	3,850 CF	2.15	8,277.50	1.62	6,237.00	1.00	3,850.00
19.	Install Slab SOD	5,130 SY	4.00	20,520.00	6.00	30,780.00	4.00	20,520.00
<b>Total BASE BID [items "1." through "19."]:</b>			<b>\$</b>	<b>395,225.50</b>	<b>\$</b>	<b>414,033.00</b>	<b>\$</b>	<b>428,458.00</b>

Notes to Bid Opening:

Certified Correct:

  
T. C. Spangler, Jr., P.E.

16-Oct-2015

Date

# Bid Tabulation

## Pine Hill Forest Sewer Rehabilitation

for the City of Hammond

Bid Opening: Friday, October 16, 2015, 10:00 a.m.

Engineer: Spangler Engineering, LLC

Bid Item	Description	Bid Quantity	Lawson-Bonet Constr.			Magnolia Construction		
			Unit Price	Extension	Unit Price	Extension	Unit Price	Extension
1.	Mobilization	1 EA	\$ 2,000.00	\$ 2,000.00	\$ 44,000.00	\$ 44,000.00	\$ -	\$ -
2.	Install/Open Cut 8" SS Main - 0' - 6' deep	4,020 LF	20.75	83,415.00	28.00	112,560.00	-	-
3.	Install/Open Cut 8" SS Main - 6' - 10' deep	540 LF	26.80	14,472.00	29.00	15,660.00	-	-
4.	Install new SSMH complete	17 EA	1,692.00	28,764.00	3,240.00	55,080.00	-	-
5.	Install 8x4 SS Wyes	80 EA	83.65	6,692.00	32.00	2,560.00	-	-
6.	Install/open cut 4" PVC SS Service Lateral	1,150 LF	17.40	20,010.00	34.60	39,790.00	-	-
7.	Jack & bore 4" PVC SS service lateral	1,000 LF	28.70	28,700.00	38.20	38,200.00	-	-
8.	Install/open cut 6" PVC SS Service Lateral	40 LF	19.15	766.00	37.00	1,480.00	-	-
9.	Jack & bore 6" PVC SS service lateral	20 LF	44.25	885.00	38.00	760.00	-	-
10.	Tie-in exist. Svc. to new 4"/6" svc. [incl. cleanout]	70 EA	496.20	34,734.00	445.00	31,150.00	-	-
11.	Install Cleanout on new 4"/6" SS Svc. Lateral	70 EA	405.00	28,350.00	361.00	25,270.00	-	-
12.	Miscellaneous Clearing & Sitework	1 EA	26,602.00	26,602.00	11,000.00	11,000.00	-	-
13.	Remove/replace Pavement (6" th.) - 30 driveways	686.0 SY	89.00	61,054.00	85.00	58,310.00	-	-
14.	Remove/replace Pavement (8" th.) - 5 street xings	260.0 SY	131.00	34,060.00	84.00	21,840.00	-	-
15.	Haul-in/compact BACKFILL (truck measure)	60 CY	15.40	924.00	25.00	1,500.00	-	-
16.	Haul-in/grade LIMESTONE (truck measure)	260.0 TN	52.75	13,715.00	40.00	10,400.00	-	-
17.	Sawcut pavements (4" - 8" thick)	1,600 LF	6.10	9,760.00	6.70	10,720.00	-	-
18.	Haul-in/fine grade ROOT ZONE matl. (1.0" thick)	3,850 CF	3.60	13,860.00	0.80	3,080.00	-	-
19.	Install Slab SOD	5,130 SY	6.60	33,858.00	4.40	22,572.00	-	-
<b>Total BASE BID [Items "1" through "19":]</b>			<b>\$</b>	<b>442,621.00</b>	<b>\$</b>	<b>505,932.00</b>	<b>\$</b>	<b>-</b>

Notes to Bid Opening: (b)

Certified Correct:

  
T. C. Spangler, Jr., P.E.

16-Oct-2015

Date